826

MYSORE DIVISION (OPEN LINES).

Notification dated 17th July 1930.

Sealed Tenders are invited for the following works in connection with the Remodelling of Mysore Station. Individual or separate tenders should be sent for each of the works which will be disposed of separately on their merits.

1. Earthwork for making bank.
2. Extending 1—6 feet arched Bridge No. 755.
3. Extending existing Goods shed.
4. Constructing additional goods shed.
5. Constructing goods platform wall.
6. Dismantling and re-constructing the Police Station.
7. Extending Carriage Examiner's Office by 50 feet.

2. Tenders should be submitted in special forms which can be obtained from the Executive Engineer, Mysore Railways, Mysore Division, on payment of Rupee one for a form, which amount is not refundable under any circumstances.

3. Tenders should be addressed to the Executive Engineer, Mysore Division, Railways, Mysore, the sealed covers superscribed, Tender for Item No.....(Name of work), and should reach him not later than 4 P.M. on the 9th August 1930.

4. No tender will be considered which is not on the prescribed form.

5. The rates should be noted both in figures and words. Tenders which quote rates as "Estimated rates" or "some per cent more or less than estimate rates", will not be considered.

6. The work should be completed within the period noted for each work, guaranteeing the rate of monthly progress.

7. The names of the accepted tenderers will be posted on the Notice Board of the Executive Engineer's Office by 8th September 1930, and no enquiries regarding the acceptance or rejection of tenders will be replied.

8. The final acceptance of the tender will rest with the Engineer-in-Chief, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders or any portion of any one tender.

9. Every tender should be accompanied by a Cash Receipt for the prescribed earnest money paid to the Auditor, Mysore Railways, Mysore, duly intimating the Auditor for what works in this Notification the earnest money has been paid.

10. The earnest money of unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of.

11. Successful tenderers should deposit with the Auditor, Mysore Railways, Mysore, before they sign the Schedule Agreement, five per cent of the value of work given out to them, such deposits not to exceed Rs. 1,000.

12. Tenders which are not accompanied with the receipt for earnest money paid to the Auditor as specified in para 9 *supra* will not be considered.

13. Successful tenderers should execute within eight days of the date of notification of acceptance of tenders, the usual Railway Schedule Agreement. Failure to comply with this condition will render the contract null and void and the earnest money forfeited.

14. Work should be started within 15 days from the date of acceptance of tenders. The accompanying schedules give the approximate quantity of works to be executed and this quantity is not guaranteed.

15. The time limit for completion of works referred to in para 6 *supra* should be strictly adhered to and any violation of this will render the contractor liable to forfeit his deposit amount not as a penalty or penalties but as ascertained and liquidated damages recoverable accordingly.

16. Plans, specifications and other details of works to be done are available for inspection in the Executive Engineer's Office, Mysore, where intending contractors may call and obtain any information during office hours.

In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Engineer-in-Chief will be final and legally binding.

EARTHWORK.

Earnest money Rs. 100. Work to be completed in two months.

Serial No.	Particulars	Unit	Quantity
		C.ft.	Units
1	Cutting the high ground opposite to the Station building, Mysore, in all soils including blasting rock, where necessary and depositing the spoil to form a bank on both sides of 1—6' arch bridge near Permanent Way Inspector's Office.	1,000	100
	NOTE.—(1) Rates quoted should include charges for carrying earth by head load or Ballast Train whichever convenient. All charges for the use of Ballast Train if necessary, to be paid by the contractor.		
	(2) Payments will be made on section measurements, for cutting or excavation done neatly as marked.		

EXTENDING 1—6' ARCHED BRIDGE No. 755.

Earnest money Rs. 100. Work to be completed in three months.

		C.ft.	
1	Earthwork excavating foundations in all soils including rock except blasting.	1,000	3 517
1(a)	Blasting rock	1,000	1,000
2	Concrete broken stone jelly in sand mortar	100	11·72
3	Size stone in sand mortar (coursed rubble, first sort) ...	100	46·52
4	Cut stone arch work in sand mortar including centering charges.	100	132
5	Cement pointing	Sqr.	8·98
6	Removing and resetting in sand mortar coping burnt stone slabs including cement pointing.	S.ft.	111

Note.—Specification for works will be according to Marvat's Hand Book, Vol. I.

EXTENDING THE EXISTING GOODS SHED AT MYSORE.

Earnest money Rs. 200. Work to be completed in four months.

1	Earthwork excavation of foundation, in all soils ...	C.ft. 1,000	5,700
2	Filling in basement from excavated earth of foundation ..	1,000 C.ft.	2,400
3	Concrete broken stones in sand mortar	100	2,400
4	Size stone in sand mortar (coursed rubble, first sort) ...	C.ft. 100	8,015
5	Supplying and fixing burnt stone slabs 6" thick dressed for lintels of door.	S.ft.	558
6	Cement pointing	Sqr.	81·73
7	Hoisting and fixing roofing and other iron materials (supplied departmentally).—		
	(a) R. S. Beams over gaps of doors ...	Cwt.	6·4
	(b) Roof truss 20 feet span for main building purlins, etc., including rafters for verandahs on either side assembling where necessary.	"	157
	(c) Iron doors and ventilators	"	20
	(d) Fixing Asbestos Corrugated sheet roofing, including ridging, wind ties, etc., complete.	Sqr	56·7
8	Flooring with 6" burnt stone slabs dressed, over 6" concrete of broken stone in mortar with cement pointing, etc., complete.	"	34·3
9	Supplying and fixing dressed stone pillars including the cutting of grooves for fixing bressummers.	S.ft.	120
10	Silicate painting for all iron works	Sqr.	50
11	Removing and refixing circular ventilators .. .	No.	1
12	Unloading roofing and other materials from wagons and stacking them.	Ton	30

3

CONSTRUCTING AN ADDITIONAL GOODS SHED.

Earnest money Rs. 300. Work to be completed in six months.

Sl. No.	Particulars	Unit	Approximate quantity
1	Earthwork excavation of foundation, in all soils ...	C.ft. 1,000	12,200
2	Filling in basement from excavated earth of foundation ...	1,000 C.ft.	7,000
3	Concrete broken stone in sand mortar ...	100	3,600
4	Size stone in sand mortar (coursed rubble, first sort) ...	C.ft.	17,800
5	Supplying and fixing burnt stone slabs 6" thick dressed for lintels of doors and windows.	S.ft.	712
6	Cement pointing	Sqr.	165
7	Hoisting, fixing and roofing and other iron materials (supplied departmentally.)—		
	(a) R. S. Beams over gaps of doors	Cwt.	12
	(b) Roof truss 20 feet span for main building, purlins, etc., including rafters for verandahs on either side assembling where necessary.	,,	230
	(c) Iron doors and ventilators	,,	30
	(d) Fixing Asbestos Corrugated sheet roofing, including ridging, wind ties, etc., complete.	Sqr.	98·8
	(e) Expanded Metal partition wall with angle iron frame as per plan	S.ft.	170
8	Flooring with 6" burnt stone slabs dressed, over 6" concrete of broken stone in mortar with cement pointing, etc., complete.	Sqr.	56·8
9	Silicate painting for all iron works	,,	110
10	Unloading roofing and other materials from wagons and stacking them.	Ton	55

CONSTRUCTING GOODS PLATFORM WALLS.

Earnest money Rs. 100. Work to be completed in three months.

Sl. No.	Particulars	Unit	Quantity
1	Earthwork excavating for foundations in all soils excepting blasting rock.	C.ft. 1,000	8,000
1 (a)	Filling in basement from excavated earth of foundations ...	1,000 C.ft.	5,000
2	Concrete broken stone in sand mortar	100 C.ft.	17·2
2 (a)	Size stone in sand mortar including bond stones (course rubble first sort.)	100 C.ft.	38·50
3	Fixing in position 41¼ lb. rails including fishing and fixing of cross bolts, drilling holes in rails, etc., for platform coping, complete (rails supplied Departmentally.)	R.ft.	1,728
4	Cement concrete for coping between rails and completing the surface, etc., complete.	100 C.ft.	432
5	Cement pointing	Sqr.	24·8

Note.—Specifications for work will be according to Maryat's Hand Book Part I.

DISMANTLING AND RE-CONSTRUCTING THE POLICE STATION AT MYSORE.

Earnest money Rs. 100. Work to be completed in three months.

Sl. No.	Particulars	Unit	Quantity
1	Earthwork excavating for foundations in all soils ...	C.ft. 1,000	1·539
2	Concrete broken stone in sand mortar	100	6.70
3	Burnt brick in sand mortar	C.ft.	10·85
4	Burnt brick in clay	„	21·75
5	Supplying and fixing burnt stone slabs, 6" thick dressed ...	S.ft.	237
6	Teakwood doors with battened shutters	„	64
7	Do with barred shutters	„	33
8	Teakwood ventilators with glazed shutters and iron bars, etc., complete.	„	24
9	Removing existing doors, cleaning, repairing and refixing them in position.	No.	1
10	Do windows	„	3
11	Teakwood wrought and put up including two coats of wood oiling.	C.ft.	40·3
12	Removing existing teakwood rafters, etc., cleaning and refixing them in position including two coats of wood oiling.	C.ft.	14·84
13	Roofing with Mangalore tiles (supplied by Department) over 2" x 1" teak reepers including chunam borders, wood oiling reepers, etc., complete.	Sqr.	3·15
14	Removing Mangalore tiles and reepers from the existing building, cleaning them and reroofing including chunam borders, wood oiling reepers, etc., complete.	„	9·73
15	Removing Mangalore ridge tiles from the existing building, cleaning and refixing them in mortar.	R.ft.	40
16	Flooring with 2" cuddapah slabs (supplied by Department) over 4" concrete broken stone in sand mortar with cement pointing, etc., complete.	Sqr.	7·48
17	Cut stone pillars 7' long and 9" square with base and capital, etc., complete as per approved design	No.	2
18	Cutting, hoisting and fixing second hand 41¼ lbs. rails in position.	R.ft.	63
19	Chunam plastering	Sqr.	46·55
20	Colour and white-washing, two coats	„	46·55
21	Teak-wood ornamental eave board 9" x 1" as per approved design including silicate painting.	R.ft.	150
22	Teak-wood finials, length over all 3 feet	No.	3
23	Do pendents do	„	4
24	Silicate painting two coats	Sqr.	3·5
25	Dismantling masonry, stacking and removing debris ...	C ft.	1,500

Note.—Specification for works will be according to Maryat's Hand Book, Vol. I.

EXTENDING CARRIAGE EXAMINER'S OFFICE.

Earnest money Rs. 100. Work to be completed in three months.

Sl. No.	Particulars	Unit	Quantity
1	Earthwork excavating for foundations in all soils ...	1,000 C.ft.	1·200
1(a)	Filling in basement from excavated earth of foundations ...	1,000 „	1,200
2	Concrete broken stone in sand mortar as per specification ...	100 „	5·12
3	Size stone in sand mortar (coursed rubble first sort) ...	100 „	487
4	Burnt brick in sand mortar	Do	17·76
5	Supplying and fixing burnt stone slabs 6" thick dressed ..	S.ft.	153
6	Chunam plastering	Sqr.	35·0
7	White and colour washing	„	35·0

Sl. No.	Particulars	Unit	Quantity
8	Teakwood doors with battened shutters	S.ft.	88
9	Teakwood windows with battened shutters and iron bars, etc., complete.	„	144
10	Removing and refixing windows	No.	2
11	Teakwood wrought and put up including two coats of wood oiling.	C.ft.	70·95
12	Roofing with Mangalore tiles supplied by Department, over 2" x 1" teakwood reepers including chunam borders, wood oiling reepers, etc., complete.	Sqr.	12·36
13	Fixing ridge tiles supplied by Department in mortar ...	R.ft.	52
14	Flooring with 2" cuddapah slabs over 4" concrete of broken stone in sand mortar including cement pointing (cuddapah slabs supplied Departmentally).	Sqr.	10·54
15	Teakwood ornamental eaves board 9" x 1" as per approved design including silicate painting.	R.ft.	103
16	Dismantling old brick masonry	C.ft.	24
17	Silicate painting 2 coats, doors and windows	Sqr.	6·54
18	Removing, cleaning and refixing eave board including silicate painting.	R.ft.	24

Note.—Specification for works will be according to Maryat's Hand Book, Vol. I.

Y. K. RAMACHANDRA RAU,
Executive Engineer.

MYSORE DIVISION.

Dated 3rd July 1930.

"Reference is invited to the advertisement published in detail notification in the *Mysore Gazette*, dated 10th July 1930, intimating last date of tender for 'Improving and Metalling the road leading to Bebi Hill Temple,' Nagamangala Taluk".

N. G. KRISHNAIENGAR,
Executive Engineer.

NEW BANGALORE WATER WORKS DIVISION.

Abstract Notification.

The attention of the public is invited to the detailed notice inviting sealed tenders for supplying the materials in the Material Yard at Thippagondanahalli, published on pages 804 and 805 of Part VI, of the *Mysore Gazette*, dated 17th July 1930. The last date for the presentation of tenders is 5 P.M. of 24th July 1930.

H. R. VENKATASUBBA RAO,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, DAM CONSTRUCTION AND No. I, CANAL DIVISION, KRISHNARAJASAGARA.

Dated 21st July 1930.

In modification of this office Notification, dated 30th June 1930, published on page 771, Part VI of the *Mysore Gazette*, dated 10th July 1930, the Public are hereby informed that the unserviceable articles referred to therein, will be sold, on receipt of quotations. Hence sealed covers enclosing:—(1) Rates of offer for each article will be received by the undersigned upto the 11th August 1930 The rates should be expressed in words as well as in figures, (2) the name of successful tender will be posted in the Notice Board of the Executive Engineer's Office, Krishnarajasagara and he should pay the cost of the articles and remove them within a week from the date of sale, (3) for the due fulfilment of the above condition, the purchaser will be required to execute a bond to the above effect and deposit a sum of Rs. 100 which he will forfeit in case of default, (4) the articles are available for inspection and the intending purchasers can have a look at them in the General Stores, North and South Banks, Krishnarajasagara and (5) the final acceptance of the offer will rest with the Superintending Engineer, Krishnarajasagara Circle, Mysore, who does not bind himself to accept any tender or to assign any reason, whatever for the rejection of any tender.

Abstract Notification dated the 30th June 1930.

The attention of the public is invited to the sale notification of unserviceable articles in the Dam Construction and No. I, Irwin Canal Division, published on pages 771 and 772, Part VI of the *Mysore Gazette*, dated 10th July 1930.

N. SARABHOJA,
Executive Engineer.